



Mililani Memorial Park Mauka Chapel

Date:	March 1992 — April 1993
Location:	Mililani, Oahu, Hawaii
Cost:	\$5,500,000
Client:	Mililani Memorial Group

Project Description

The project consisted of a 21,000 square foot, one-story building at the Mililani Memorial Park. Walls were reinforced concrete, CMU, and stud walls with EFS. The roof framing consisted of pre-fabricated wood trusses with plywood sheathing and the chapel roof consisted of large pre-shaped laminated wood columns and arches. Interior finishes were metal framing with gypsum board surfaces, painting, carpet and VCT flooring. Stained glass windows were installed in the chapel area. HVAC, power, lighting, and telecom were also included. Exterior work comprised of site excavation and grading, an asphalt parking lot, utilities, and sewage treatment facility.

